



Figure 60 This strap tie-down was bent after the concrete was poured, which spalled the concrete and did not enhance the strap's capacity. The arrows highlight panel nailing. Nailing to the post behind the strap tie-down should match the panel edge nailing, but only about half the required nails are present.